



Overview of the SKA

Richard Schilizzi

Signal Processing Conceptual Design Review
14 April 2011

This talk



- SKA overview
- Science drivers
- Baseline Design
- Advanced Instrumentation Program
- Engineering progress
- Pre-construction phase
- Governance
- Site selection
- Schedule

Timeline



- 1995-00 Preliminary R&D
- 2000-07 Initial Concept Phase
- 2008-12 Preparatory Phase
 - System design
- 2012-15 Pre-construction Phase
 - Detailed design, Production readiness
- 2016-23 Construction
- 2020-50+ Operations

Top-level description



a large radio telescope for transformational science

- up to 1 million m² collecting area distributed over a distance of 3000+ km
- operating as an interferometer at frequencies from 70 MHz to 10 GHz (4m-3cm) with two or more detector technologies
- connected to a signal processor and high performance computing system by an optical fibre network

providing

- 40 x sensitivity of EVLA, and
- up to 10000 x survey speed

67 institutes in 20 countries are participating



The Square Kilometre Array

Top-level description (2)



Construction will proceed in two phases:

SKA_1 , SKA_2

SKA_1 will be a subset ($\sim 10\%$) of SKA_2

Major science observations already possible with SKA_1 in 2020

Phased construction allows maximum use of advances in technology



Science Drivers

Exploring the Universe with the world's largest radio telescope

SKA₂ Key Science Drivers

ORIGINS

- Neutral hydrogen in the universe from the Epoch of Re-ionisation to now

When did the first stars and galaxies form?
How did galaxies evolve?
Dark Energy, Dark Matter


- Astro-biology

FUNDAMENTAL FORCES

- Pulsars, General Relativity & gravitational waves

- Origin & evolution of cosmic magnetism

TRANSIENTS (NEW PHENOMENA)



*Science with the
Square Kilometre
Array*

(2004, eds. C. Carilli
& S. Rawlings, *New
Astron. Rev.*, **48**)

SKA₁ Key Science Drivers


ORIGINS

- Neutral hydrogen in the universe from the Epoch of Re-ionisation to now

When did the first stars and galaxies form?
How did galaxies evolve?
Dark Energy, dark matter

FUNDAMENTAL FORCES

- Pulsars, General Relativity & gravitational waves



*Science with the
Square Kilometre
Array*

(2004, eds. C. Carilli
& S. Rawlings, *New
Astron. Rev.*, **48**)




Baseline design and Advanced Instrumentation Program

Exploring the Universe with the world's largest radio telescope

SKA₁ baseline design



Baseline technologies are mature and demonstrated in the SKA Precursors and Pathfinders



Artist renditions from Swinburne Astronomy Productions
Exploring the Universe with the world's largest radio telescope

Advanced Instrumentation Program




1. Development of innovative wide-field “radio camera” technologies at mid-frequencies
 - phased array feeds (PAFs) on the dishes (FoV ~ 30 deg²)
 - mid-frequency aperture array (FoV ~ 200 deg²)
2. Ultra-wideband single pixel feeds

The AIP is designed to build maturity and retire risk

Has the potential for enhancing SKA₁ and being a major part of SKA₂

- Evaluation point in 2014
- Final decision in 2016

SKA₂ including AIP technologies



Artist renditions from Swinburne Astronomy Productions

SKA is driving development of new science & technical solutions



- Dishes, feeds, receivers (N=3000)
 - Low and mid aperture arrays (N=250)
 - Signal transport (10 Pbit/s)
 - Signal processing (exa-MACs)
 - Software engineering and algorithm development
 - High performance computing (exa-flop capability)
 - Data storage (exa-byte capacity)
 - (Distributed) power requirements (50 -100 MW)
- } ongoing verification programs

INDUSTRY ENGAGEMENT IS CENTRAL TO THE SKA



Current engineering developments

SKA System Design (2007-2012)



Contributing programs


EC FP6 SKA Design Study (SKADS)

EC FP7 Preparatory Phase (PrepSKA)

US Technology Development Program

“Precursor” telescopes on the candidate sites
(ASKAP (AU), MeerKAT (SA))

“Pathfinder” telescopes like LOFAR, APERTIF



Baseline design component: Low frequency aperture arrays



LOFAR (Netherlands et al)



MWA (USA, Australia, India)

Exploring the Universe with the world's largest radio telescope


Baseline design component: Dishes + single pivot feeds



ATA (U)
42x6m
hydroform
dishes




ASKAP
36x12m





**SKA Dish Verification
Antenna #1**

Mechanical design by
Gordon Lacy & Matt Fleming



10 m composite prototype

Advanced Instrumentation Program: dishes+multi-pixel feeds



DRAO
Canada

Exploring the Universe with the world's largest radio telescope


Advanced Instrumentation Program: mid-frequency aperture array




EMBRACE



FP6-
SKADS



2-PAD




...ring the Universe with the world's largest radio telescope

Advanced Instrumentation Program: wide-band single pixel feeds





**Quad
ridge
Lindgren
horn**



**Quasi Self
Complementary
feed**



ATA feed



**Chalmers
"Eleven"
feed**



**Inverted conical
sinuous feed**

From German Cortes Exploring the Universe

Signal transport, signal processing, computing




The *EXPR*es network



Network status as per 2008-05-02. Image created by Paul Bowen <bowen@jive.nl>. Satellite image: Blue Marble Next Generation, courtesy of NASA Visible Earth (visibleearth.nasa.gov).



Fiber optic transmission






Current task in 2011 and 2012 is to convert this SKA-relevant design and development into PDR-ready SKA-specific designs and costs

Conceptual Design Reviews in 2011




- 23-25 Feb System delta-CoDR on SKA₁
- 14-15 Apr Signal Processing
- 19-20 Apr Aperture Arrays
- 28-30 Jun Signal Transport & Networks
- 13-15 July Dish and Dish Arrays
 - 2-3 Feb Dish Verification Antenna #1
- 12-14 Oct Software & Computing

Schedule: Preparatory Phase → Preconstruction Phase → SKA₁ Construction



Schedule: SKA₁ Construction → SKA₂ construction



Legend
 CoDR – Concept design review
 SRR – (Sub)System Requirements Review
 PDR – Preliminary Design Review
 CDR – Critical Design Review
 PR – Production Review
 TRR – Test Readiness Review
 SAT – Site Acceptance Test
 REV – Review
 AA – Aperture Array
 DRM – Design Reference Mission

Pre-construction phase



Goals

1. Progress the SKA design to Production Readiness Review stage and let contracts for construction of major sub-systems
2. Progress infrastructure roll-out on selected site to allow sub-systems to be deployed
3. Mature the SKA legal entity into an organisation capable of carrying out the construction, verification, and operation of the telescope

Work Packages in the Project Execution Plan



1. Management
2. System
3. Science
4. Maintenance and support /Operations Plan
5. Dishes
6. Aperture arrays
7. Signal transport & networks
8. Signal processing
9. Computing & software
10. Power
11. Site preparation

Approach



- Strong central project office (SPO) with management and system design authority to ensure a coherent and effective effort.
 - System oversight and system-oriented leadership
- Employ an industry culture in managing and costing the project
- Close engagement of industry essential throughout Pre-Construction phase
- SPO will contract work on major sub-systems to a small number of Work Package Contractors (WPCs)

Resource Summary for 2012 - 2015



Total resources proposed (4 years): 90.9 M€

WPCs: 63.0 M€ (70%)

SPO: 27.9 M€ (30%)




Status of the project

Former governance structure: April 2008 – March 2011



Agencies SKA
Group (ASG)

PrepSKA Board



PrepSKA: 7 work packages



WP1 PrepSKA management (STFC, U Oxford, U Manch'r)

WP2 Costed telescope design (SPDO)

WP3 Further site characterization in Australia+NZ
and Southern Africa (SPDO)

WP4 Governance (NWO, NL)

WP5 Procurement and involvement of industry INAF, Italy)

WP6 Options for funding (STFC, UK)

WP7 Impact on broad government priorities (U Manchester)

All WPs will be completed by 31 March 2012

Interim governance (April-July 2011)




Founding Board Signatories

Australia
China
France
Germany
Italy
Netherlands
New Zealand
South Africa
UK

Tasks


1. Establish a legal entity for the SKA Organisation by July 2011
 2. Decide location of the SKA Project Office **Jodrell Bank Observatory**
 3. Agree a resourced Project Execution Plan for the pre-Construction Phase
 4. Start recruitment of the SPO Director
-

Interim governance (July - Dec 2011)



diverse with the world's largest radio telescope

Governance: January 2012 →



Site selection



Physical requirements

- Extremely radio quiet environment
- At least 3000 km in extent
- Low ionospheric turbulence
- Low tropospheric turbulence

Two candidates short-listed in 2006

Site selection process






Image © 2007 Terrametrics
Image NASA

Google

South Africa + 7 countries



0 1000 2000 3000 km

largest radio telescope

Top level schedule for the SKA



Technical

- 2008-12 telescope system design and cost
- 2013-15 detailed design in the pre-construction phase
- 2016-19 Phase 1 construction
- 2016 Advanced Instrumentation Program decision
- 2018-23 Phase 2 construction
- 2020→ full science operations with Phase 1
- 2024→ full science operations with Phase 2

Programmatic

- 2011 approve funding for pre-construction phase
establish SKA organisation as a legal entity
select location for SKA Project Office
- 2012 site selection
- 2014 approve construction funding for Phase 1 (350 M€, 2007)
- 2018 approve construction funding for Phase 2 (1.2 B€, 2007)



END