


Integration Test Facilities

Proposal



SQUARE KILOMETRE ARRAY

Exploring the Universe with the world's largest radio telescope

David Bolt & Adam MacLeod

12 Nov 2015

Introduction

- What is the Integration Test Facility Concept?
 - ITF is a general term. Can refer to any facility for performing integration testing at any level of the project.
 - For SKA we anticipate three tiers of ITF:
 - Element/contractor level ITF
 - Development testing of elements in isolation
 - Simulated interfaces
 - Rigorous testing of boundary conditions
 - System Level ITF
 - Elements are integrated and tested together for the first time
 - Validate L2 (element level interfaces)
 - Demonstrate higher-level functionality
 - On Site ITF
 - Elements are assembled, integrated and verified on site (or in situ)
 - As part of the growing / evolving telescopes
 - Supporting verification and validation of L1 requirements.

In this presentation we are discussing the purpose and scope of these specific ITFs.



Overview

- System Level ITF
 - Elements are integrated and tested together for the first time
 - Validate L2 (element level interfaces)
 - Demonstrate higher-level functionality
- These ITFs are not currently in scope of the project.
 - Wide acceptance that such facilities are needed.
- AIV is leading the work on advancing the concept and promoting these facilities.
 - Significant overlap with AIV's areas of responsibility
 - Significant overlap with AIV's areas of expertise

Purpose/Benefit of the ITF

- This facility will support initial integration of **complex** SKA1 sub-systems as part of a larger system.
 - It should allow interfaces and interoperability of the sub-systems to be demonstrated and fully tested.
 - It should provide a convenient environment for collaboration between teams working in different technical domains.
 - It should support early identification of issues and early retirement of risks.
 - It should allow ease of fault isolation and issue resolution. Most first-stage integration work is either impractical or infeasible to do at site.


Purpose/Benefit of the ITFs

- For the contractors
 - Prove their interfaces. Isolate and address issues in a benign environment.
 - Knowledge transfer.
 - Facilitate incremental enhancements and regression testing.
 - Prove Integration Readiness as a part of sell off.
- For the AIV entity
 - Knowledge transfer. Observe and learn how to operate the subsystems.
 - Input into Integration Readiness/Handover quality gate.

Concept of the ITF

- SKA1 subsystems that would have first-stage integration at the ITF include those being designed by:
 - Dish and LFAA (Receivers and Beamformers),
 - CSP (Correlator and Pulsar Search Engines),
 - SDP (Science Processing Pipeline software & minimal HW),
 - SADT (Network Infrastructure, Data Transport, Timing and Synchronisation),
 - TM (Telescope Manager software and hardware),
 - INFRA-AUS / SA (Racks with cooling and power distribution).

Overview of Telescope Roll Out



Concept of the ITF

- The ITF system under test would be similar to AR1
 - Complete receive chains for at >4 dishes/stations, through to a correlator.
 - Support for simulated analog and digital inputs.
 - Basic facilities for performing Science Data Processing.
 - Supporting subsystems from SaDT, TM and INFRA
- The system would be maintained throughout construction
 - With representative versions of the respective elements.
 - Does not need to scale in size.
 - Wherever practical, functional enhancements and bug fixes would be tested and verified in the ITF before being deployed to site.

Concept of the ITF

- The ITFs will be used throughout the entire construction phase.
 - It would also be a useful resource to have pre and post construction.
- Most testing will be done by the contractors with oversight by the AIV entity.
 - Testing can be quite informal.
 - However CM will be a necessity.
 - 24 hour and remote access may be requirements
- The ITFs are not a production support facility.
 - It is used for qualification of the designs.
 - Including incremental enhancements and bug fixes.
 - A part of demonstrating Integration Readiness of configuration items.
- As a staging facility operated by the AIV entity, it may be suitable to have ITFs in each host country.
- The ITF concept may be expanded.
 - Through the addition of centralised EMC test facilities and laboratory environments.

AIV Next Steps

- Refinement of the concept
 - Business case and derived requirements
 - Bringing the ITFs into scope of the project
 - Increased detail on contractor input to the ITF (functionality and timelines, labour support)
 - Increased detail on the output of the ITF (L2 verification, contractor sell-off, integration readiness & handover, L1 verification)
 - This requires help from the consortia!

- To be reflected in AIV documentation including the Roll Out Plans, the Handover Checklist and (probably) the cost model.

SQUARE KILOMETRE ARRAY

Exploring the Universe with the world's largest radio telescope

