

# The Advanced Virgo Project Office a Report from the Field

Franco Carbognani

*on behalf of the Virgo Collaboration*

2017 SKA Engineering Meeting

Rotterdam, 15/06/2017

- Detecting GWs with Interferometers
- Advanced Virgo (AdV)
- The AdV Project Office
- The AdV Project Management
- A Procurement Case: the CB Scaffolding
- A Project “Crisis” Case: Monolithic Suspension Failure
- Conclusions

## Effect of GWs:

Squeeze and stretch the space in perpendicular directions: strain

$$h = \Delta L / L$$

## We'll need:

A set of free test masses, far apart,

A means to measure their relative motion, and

Isolation of the masses from other causes of motion.

## Here's the challenge:

Even for the most tremendous events in Universe,  $h \sim 10^{-21}$

If test masses are separated by 3 km, that means a **length change less than  $10^{-18}\text{m}$ !**


Laser used to measure relative lengths of two orthogonal arms

Arms are few km

Measure difference in length to one part in  $10^{21}$  or  $10^{-18}$  meters

...causing the interference pattern to change at the photodiode


As a wave passes, the arm lengths change in different ways....



# 1<sup>st</sup> Generation and Advanced Detectors


LIGO and Virgo achieved the nominal sensitivity set more than a decade ago with good duty cycle during science runs but no detections were made

- A next generation of machines, was designed and constructed
  - 10 x sensitivity improvement over 1st generation
  - 1000 x increase of observation volume
  - 1 day of AdV data >> 1 yrs of Virgo data





# A Bit of History



# The GW astronomy era has begun (and is awaiting for us...)



**SNR=23.7**  
**FAR <  $6 \cdot 10^{-7} \text{ yr}^{-1}$**   
**Significance >  $5.3 \sigma$**

**SNR=9.7**  
**FAR =  $0.37 \text{ yr}^{-1}$**   
**Significance =  $1.7 \sigma$**

**SNR=13.0**  
**FAR <  $6 \cdot 10^{-7} \text{ yr}^{-1}$**   
**Significance >  $5.3 \sigma$**

Image credit: LIGO






# Sky location

GW laser interferometers are not pointing telescopes

Sky location can be reconstructed through the time of arrival of GW radiation at the different detector sites, as well as the relative amplitude and phase of the GWs in different detectors

In the design LIGO-Virgo network, GW150914 could have been localized to less than  $20 \text{ deg}^2$

GW150914 sky location is with large uncertainty



LVC - Living Rev. Relativity, 19, (2016),1



# Advanced Virgo

- ❑ Advanced Virgo (AdV): upgrade of the Virgo interferometric detector
- ❑ Participated by scientists from France and Italy (former founders of Virgo), The Netherlands, Poland and Hungary
- ❑ Funding approved in Dec 2009 (21.8 ME + Nikhef in kind contribution)
- ❑ End of installation: July 2016
- ❑ Part of the international network (MoU with LSC)
- ❑ Short-term goal: join O2b in ~March 2017

6 European countries  
20 labs, ~250 authors


APC Paris  
ARTEMIS Nice  
EGO Cascina  
INFN Firenze-Urbino  
INFN Genova  
INFN Napoli  
INFN Perugia  
INFN Pisa  
INFN Roma La Sapienza  
INFN Roma Tor Vergata  
INFN Trento-Padova  
LAL Orsay - ESPCI Paris  
LAPP Annecy  
LKB Paris  
LMA Lyon  
NIKHEF Amsterdam  
POLGRAW(Poland)  
Radboud Uni. Nijmegen  
RMKI Budapest  
Univ. of Valencia



# AdV Detector Design



## MAIN CHANGES wrt Virgo

- larger beam
- heavier mirrors
- higher quality optics
- thermal control of aberrations
- thorough stray light control
- better vacuum




# AdV Commissioning Progress


- Last mirror (WE) suspended in July 2016
- November 2016, full ITF available for commissioning
- First lock at half fringe (December 30th)
- February 2017, ITF locked at dark fringe for 15 minutes
- June 2017, ITF operational and automated, noise hunting fully ongoing. Performed the first 3 days engineering run








# AdV Project Office: Structure



- *Lessons learned: Get ready as early as possible to deal with construction site(s) specific legislation, in particular for safety (hoping they are not changing it in the meantime.....)*



# AdV Management Chart





## On-site works coordination

- Advanced Virgo Works Requests Tracking (WRT) System: use [this link](#) for submitting a work request.
- [Minutes](#) of the weekly on-site works coordination meetings.
- Short/mid term on-site works [planning](#) (MPP/PDF).

## Long-term planning and project resources

- The long-term [AdVirgo planning](#) is in the TDS, in format MPP and PDF (planning data 16/10/2012, version -p).
  - See the "annex files" section for the 2nd WBS level planning; See "other releases" for previous versions.
  - Milestones: [SS milestone files](#), [chart](#)
  - [Critical path](#) (16/10/12)
  - [Technical explanations](#) on the planning
- Budget
  - [Reference budget](#) (17/10/12)
  - [Report](#) of the May 2012 cost review committee.
  - [Adv financial procedures](#)
- Manpower
  - Profiles of [needed manpower](#) for Adv, each SS and each laboratory (16/10/2012)
  - Table of [available manpower](#) as reported by laboratories (16/07/2012)

## Work Breakdown Structure

- [Advanced Virgo WBS](#), derived from the Adv planning (17/10/12, -p)
- [Equivalence table](#) for different versions of the WBS codes
- [Subsystem WBS files](#). Make sure to always use the last version before changing the WBS of your SS.

## Project progress

- Archive of Advanced Virgo [Site News](#)
- [Monthly reports](#) of the Adv subsystems
- Monthly report [template](#)

## Interface control

- [List of SS interfaces](#): external dependencies and inter-SS links in global planning (17/10/2012)
- [Interface control matrix](#) with links to all existing ICD documents
- [Template](#) for interface control documents

## Risk management

- [Risk management plan](#)
- [Risk register](#): list of project risks with evaluation of probability and impact, and mitigation actions

## Configuration control

- [Adv change requests](#)


## Standardization

The following documents, not yet officially discussed, are proposed as guidelines for electronics development and integration.

- Guidelines for an electronics [systems engineering](#) approach
- Guidelines and Requirements for Electronics
  - Part I: [Installation](#)
  - Part II: [Systems](#).
- Integration of electronics in Virgo: [list of minimum requirements](#)
- Integration of electronics in Virgo: [check list form](#)

# On Site Works coordination

For the most complex activities integrated detailed planning were drafted during the weekly coordination meetings, circulated and refined considering the feedback of all involved parties



## WBS principles

Ideally 3 levels

1. Subsystem
2. Task
3. Subtask

4<sup>th</sup> level possible if needed for work attribution to laboratories.

Everything that needs budget or manpower must be in the WBS.

Include all tasks: design, prototyping, commissioning

MIR.06.03-d	Modification scatterometer [LMA]
MIR.06.04-d	New bench for high accuracy flatness measurement- Design/Manufacturing/Test [LMA]
<b>PAY</b>	
PAY.01-d	Subsystem Management [Roma1]
PAY.02-d	Recoil Mass for NE and WE Monolithic Payloads
PAY.02.01-d	Recoil Mass design [Roma1]
PAY.02.02-d	Recoil Mass prototyping [Roma1]
PAY.02.03-d	Recoil Mass production [Roma1]
PAY.02.04-d	Recoil Mass integration in NE and WE Payloads [Roma1]
PAY.03-d	Recoil Mass for NI and WI Monolithic Payloads
PAY.03.01-d	Recoil Mass design [Roma1]
PAY.03.02-d	Recoil Mass prototyping [Roma1]
PAY.03.03-d	Recoil Mass production [Roma1]
PAY.03.04-d	Recoil Mass integration in NI and WI Payloads [Roma1]
PAY.04-d	Marionette for Monolithic Payloads
PAY.04.01-d	Marionette design [Roma1]
PAY.04.02-d	Marionette production [Roma1]
PAY.04.03-d	Marionette integration [Roma1]
PAY.05-d	Marionette Recoil Mass for Monolithic Payloads

# Interface Management

## AdVirgo interface control matrix

The links in the matrix entries lead to the last version of the interface control document between the two subsystems.

	DAQ	DET	IME	INJ	ISC	MIR	OSD	PAY	PSL	SAT	TCS	VAC
DAQ		<a href="#">v0.1</a>	<a href="#">v0.1</a>					<a href="#">v0.1</a>				<a href="#">v0.1</a>
DET			<a href="#">v0.1</a>	<a href="#">v0.2</a>	<a href="#">v0.1</a>		<a href="#">v0.1</a>	<a href="#">v0.1</a>				
IME				X								<a href="#">v0.1</a>
INJ					<a href="#">v0.1</a>	X		<a href="#">v0.1</a>	<a href="#">v1.2</a>	<a href="#">v0.1</a>		X
ISC							<a href="#">v0.1</a>	<a href="#">v0.1</a>	X	<a href="#">v0.1</a>		
MIR							<a href="#">v0.1</a>	<a href="#">v0.1</a>			<a href="#">v0.1</a>	
OSD								<a href="#">v0.1</a>			<a href="#">v0.1</a>	
PAY										<a href="#">v0.1</a>	<a href="#">v0.1</a>	<a href="#">v0.1</a>
PSL												
SAT												<a href="#">v0.1</a>
TCS												<a href="#">v0.1</a>
VAC												

X = to be written

ICD documents version 0.1: interfaces inserted in ICD template based on the subsystem WBS information.



# Interface Management

VAC << SLC: baffles inside the central interferometer links installed

VAC << SLC: small cryotrap baffles installed

## SS external dependencies

### TCS

#### TCS external dependencies:

TCS << AdV: Start of second upgrade phase

TCS << DAQ: DAQ-Boxes with all mezzanines (ADC, DAC, detection) ready for installation

TCS << DET: Start of detection area pre-commissioning

TCS << INJ: SS precommissioning finished

TCS << INJ: SS precommissioning start

TCS << MIR: CP produced

TCS << OSD: Opt. design finalized

TCS << PAY: Detection Beam Line complete

TCS << PAY: Input payloads integrated into towers

TCS << PAY: NE integrated into tower

TCS << PAY: PR integrated into tower

TCS << PAY: WE integrated into tower

TCS << VAC: Central towers displaced

TCS << VAC: enlarged links design finalized

TCS << VAC: enlarged links installed

TCS << VAC: NE displacement finished

#### Other subsystems' external dependencies from TCS:

PAY << TCS: Ring Heater Prototype Ready

### VAC

#### VAC external dependencies:

VAC << AdV: Start of second upgrade phase

VAC << EGO: Scaffolding installation finish

< SLC < Installation < Central interferometer link baffles installation (31/10/13)

< SLC < Installation < Small cryotrap baffles installation (07/02/14)

## Connections in global planning

#### Linked to:

< MAN < AdV: Start of spending for second upgrade phase (01/07/14)

< DAQ < DAQ: DAQ-Boxes with all mezzanines (ADC, DAC, detection) ready for installation (02/05/14)

< DET < DET: Start of detection area pre-commissioning (18/11/14)

< INJ < General opto-mechanical layout, common parts construction, Installation and pre-commissioning < Pre-Commissioning (Low power) (03/03/15)

< INJ < INJ: SS precommissioning start (30/09/14)

< MIR < Coatings < 2 CP coatings (09/05/14)

< MAN < AdV: Optical design frozen (31/10/11)

< PAY < PAY: WI payload suspended and controlled (06/02/15)

< PAY < PAY: WI payload suspended and controlled (03/12/14)

< PAY < PAY: NE payload suspended and controlled (24/07/15)

< PAY < PAY: PR payload suspended and controlled (09/01/15)

< PAY < PAY: WE payload suspended and controlled (12/06/15)

< VAC < VAC: Central Towers displaced (03/04/13)

< VAC < Enlarged Links < Design finalization (with SLC) (14/02/13)

< VAC < Enlarged Links < Installation (06/03/14)

< VAC < VAC: NE displacement finished (19/06/13)

#### Linked to:

< TCS < Ring Heater < Full-scale RH prototype assembly and (05/04/13)

#### Linked to:

< MAN < AdV: Start of spending for second upgrade phase (01/07/14)

< EGO < Scaffolding < EGO: CB scaffolding installed (30/08/13)

SS depends on task from other SS

Other SS depends on task from this SS

# Risk Management

## Advanced Virgo Risk Register

Level	Probability	Level	Cost Consequence	Schedule Consequence	Performance Consequence
5	Extremely Likely – 90% probability of occurrence over the project life	5	> 300 k€	> 4 months	Unacceptable
4	Highly Likely – 70% probability of occurrence over the project life	4	50 ... 300 k€	2 - 4 months	Doesn't meet important goals
3	Moderately Likely – 50% probability of occurrence over the project life	3	25 ... 50 k€	1 - 2 months	Doesn't meet goals in some areas
2	Unlikely – 30 % probability of occurrence over the project life	2	5 ... 25 k€	<1 month	Doesn't meet high goals
1	Highly Unlikely – 10% probability of occurrence over the project life	1	< 5 k€	Negligible	Negligible

### Initial Risk Evaluation

Risk manager	Risk Event	Affected WBS code	Prob-ability	Consequence			Risk Score	Priority follow-up list	Action Date (check)	Proposed Mitigation Actions	Comments
				Cost	Sched-ule	Perform					
A.Paoli	If specifications for Detailed Design are not sufficient in view of the final Adv sensitivity, the project shall be revised.	IME.03-h, IME.05-h	1	4	3	2	Low		Dec 10	Alternative strategy: assuming high safety margins (i.e. damping platforms, increasing the distance of the machines, etc.)	
A.Paoli	Decision on electronics displacement and design can delay infrastructure support works or change costs.	IME.06-h	2	3	1	3	Med		Dec 10		
A.Paoli	Realization of clean room for the DET lab: feasibility under study for space issues. Such works will increase the cost.	IME.07-h	5	3	1	5	High		Jun 10	Verification of the feasibility to take the decision.	



## AdV CRQ 2014/002

### Continuous LN2 supply for small cryotrap

#### Abstract

The two smalltraps cryostats are presently under construction; their delivery is foreseen at the end of November 2014. In the original design of AdV they have been conceived as operating in batch mode, refilling the 200 liters reservoir twice per week, such as for the cryotrap which was functioning during +. Here we propose to install a dedicated LN2 supply line per each smalltrap, in order to operate the smalltraps in continuous mode, feeding a continuous flux of cryogen. Main advantage is to improve the duty cycle of AdV, limiting the downtime for maintenance breaks, and to improve the operational functioning of the two smalltraps.

#### Change request documents

- [VIR-0509A-14](#) AdV change request - Continuous LN2 supply for smalltraps
- [VIR-0517A-14](#) IPRB Report on the change request "Continuous LN2 Supply for smalltrap"

#### Other documents

- [VIR-0504A-14](#) Presentation at weekly meeting 06/11/2014

#### 2014

[2014/004](#) Increase of the End Mirror transmission

[2014/003](#) Clean air filtering for central building ventilation system

[2014/002](#) Continuous LN2 supply for small cryotrap

[2014/001](#) Lower clamps design modification for test-mass payloads

#### 2013

[2013/001](#) Auxiliary lasers

#### 2012

[2012/001](#) Foundations for the PAY test facility

#### 2011

[2011/001](#) Upgrade of machines for fiber pulling

## Past reviews

### ■ Acceptance reviews

- Injection/detection clean rooms: see the July 2014 report: [🔒 VIR-0384A-14](#), October report: [🔒 VIR-0457A-14](#) and the final November report: [🔒 VIR-0509A-14](#).

### ■ Installation reviews

- Questions asked to the subsystem manager for an installation review:

1. Most recent version of the planning, are the interfaces checked?
2. Status of various components: which are the missing ones?
3. Hardware data base: status of the registration of the components and their documentation?
4. What are the sensors monitoring the active devices?
5. What is the list of channels produced by the subsystem?
6. What are the acceptance criteria you propose for a possible acceptance review?

- INJ: January 2014. Final report: [🔒 VIR-0011A-14](#).


- PSL: February 2014. Final report: [🔒 VIR-0057A-14](#).

### ■ Change request reviews (see also the [🔒 AdV CRQ web page](#))

- CRE-2014/004: Increasing the end test mass transmission ([🔒 VIR-0535A-14](#)). Nov 2014 review, report: [🔒 VIR-0596A-14](#).
- CRE-2014/003: Clean air filtering for central building ventilation system([🔒 VIR-0512A-14](#)). Nov 2014 review, report: [🔒 VIR-0519A-14](#).
- CRE-2014/002: Continuous LN2 supply for small traps ([🔒 VIR-0509A-14](#)). Nov. 2014 review, report: [🔒 VIR-0521A-14](#).
- CRE-2014/001: Lower clamps design modification for test-mass payloads ([🔒 VIR-0463A-14](#)). July-Oct. 2014 review , report: [🔒 VIR-0469A-14](#).
- CRE-2013/001: Auxiliary laser wavelength change: ([🔒 VIR-0352B-13](#)). April 2014 review, report: [🔒 VIR-0204A-14](#).
- CRE-2012/001: Infrastructure modification for the PAY test facility. Oct. 2012 review, report: [🔒 VIR-0394A-12](#).
- CRE-2011/001: [🔒 Upgrade of the fiber machines](#). Sep-Nov 2011 review, report [🔒 VIR-0698A-11](#).
- CRE-2010/001: [CRE- PSL baseline change \(fiber solution\)](#). December 2010 review, report [🔒 VIR-0710A-10](#).
  - April 2015 follow up review: report [🔒 VIR-0208A-15](#).

### ■ Technical readiness reviews

- First cryolink; May 2011. Final report: [🔒 VIR-0323A-11](#).
- 100W laser: Nov-Dec 2011. Final report: [🔒 VIR-0730A-11](#).





## Advanced Virgo Quality Control Tracking System (QCT)

Logged in as: virgo (virgo - Reporter) - 2015-10-25 15:42 CEST

[Main](#)
[My View](#)
[Sheets List](#)
[New Sheet](#)
[My Account](#)
[Help](#)
[Logout](#)
[Check Sheet](#)
[Jump](#)

Example: BS03 mirror

Recently Visited: [0000057](#), [0000059](#), [0000074](#), [0000084](#)

View Check Sheets Details [ [Jump to Notes](#) ]

[ << ] [ >> ]

[ [Check Sheet History](#) ] [ [Print](#) ]

ID	Project	Subsystem	Date Submitted	Last Update
0000060	Advanced Virgo	[ ] MIR	2013-10-25 12:17	2015-10-12 20:58
Reporter	richard			
Subsystem Manager				
Status	non-compliant			
Component	0000060: Beam Splitter Mirror 03			
Required Documentation	Substrates: Data sheet (Heraeus): VIR-0614A-11: <a href="https://tds.ego-gw.it/ql/?c=8671">https://tds.ego-gw.it/ql/?c=8671</a> [^] Absorption measurements (LMA): VIR-0567A-11: <a href="https://tds.ego-gw.it/ql/?c=8624">https://tds.ego-gw.it/ql/?c=8624</a> [^] Acceptance reports: VIR-0605A-11: <a href="https://tds.ego-gw.it/ql/?c=8662">https://tds.ego-gw.it/ql/?c=8662</a> [^] VIR-0606A-11: <a href="https://tds.ego-gw.it/ql/?c=8663">https://tds.ego-gw.it/ql/?c=8663</a> [^]  Polishing: Specifications (LMA): VIR-0316A-12: <a href="https://tds.ego-gw.it/ql/?c=9137">https://tds.ego-gw.it/ql/?c=9137</a> [^] Measurements (Zygo): VIR-0378A-14: <a href="https://tds.ego-gw.it/ql/?c=10428">https://tds.ego-gw.it/ql/?c=10428</a> [^] Measurements (LMA): Mirror characterisation (LMA):			
Quality Priority Level (QPL) - Cost	4 (50 ... 300 kE)			
Quality Priority Level (QPL) - Delay	5 (> 4 months)			
Quality Priority Level (QPL) - Performance	5 (Unacceptable)			
Attached Files				

Not all documentation available yet

Available documentation

Spare - not coated yet



# Advanced Virgo Works Requests Tracking System (WRT)

Main	My View	Requests List	New Request	Work Title	Manage	My Account	Help	Logout	Issue #	Jump
------	---------	---------------	-------------	------------	--------	------------	------	--------	---------	------

Subsystem

SS

\*Work Title

Title

\*Purpose (what will be done?) and execution (how will it be done?) of works

Description

Location(s)

CB-Clean Rooms  
CB-DAQ Room  
CB-Detection Lab  
CB-EE Room  
CB-Laser Lab

Location

\*WBS Code

WBS code

\*Foreseen Starting Date

\*Foreseen Ending Date

\*Involved Persons

Involved persons / Virgo groups

\*Involved Virgo Groups

Needed support from EGO personnel

Specific Major Equipment that will be brought onsite

Needed resources

Needed EGO Equipment (tools, clean rooms, beam cranes,...)

Potential safety risks (interference with other works,...)

Safety aspects

Upload Relevant Documentation (if more than one document please upload a zip file) (Maximum size: 8,389k)

Choose...

\* required

Submit Request

# Tools: Hardware Inventory

HW inventory for keeping track of installed components


Electronics, viewports, optics, ...

Location based

Location

## Mode Cleaner Building (MCB)

This is a Building




### History:

Date	Details	User
21/11/14, 15:42	Part edited	hemming
19/11/14, 16:29	Topology saved: left 540, top: 371, height: 30, width: 33	hemming
19/11/14, 15:46	Topology saved: left 540, top: 371, height: 30, width: 33	hemming
19/11/14, 14:06	Topology saved: left 540, top: 371, height: 30, width: 33	hemming
11/02/14, 17:24	File 00017_Preboot_v001.tar deleted.	pacaud



Map

Go to: Available locations > Virgo



Items

## Tracking of individual items

Items can be modified, moved, ...: tracked in item's history log

Connections between electronics parts are managed in the HW database

Item

**rtpc12**


  

This is a Real-time PC

With the serial no: 61003213TF




  

Dual Core  
Detection NE

**Documentation:**

 intelpro1000pxe.txt

**History:**

Date	Details	User
20/11/14, 13:08	Topology saved: left 182, top: 174, height: 75, width: 196	rolland
20/11/14, 13:07	Moved from: 20.	rolland
20/11/14, 11:04	2 PCI (1) Real-time PC - rtpc12 disconnected from 6 PCI (5) Real-time PC - rtpc-test2	hemming
20/11/14, 11:04	2 PCI (1) Real-time PC - rtpc12 connected to 6 PCI (5) Real-time PC - rtpc-test2	hemming

History worklog

Connections

Go to: Available locations > Virgo > Central Building (CEB) > Level 3 (CEB-L3) > DAQ Room (CEB-L3-09) > Rack\_42U - 16


- RJ45 (eth0)
- PCI (1)
- PCI (2)
- PCI (3)
- PCI (4)
- PCI (5) **TOLM PCI - 15**
- IEEE-I394**
- RJ45 (eth1)

**Connecting information**

Currently connecting: ieee-i394 7 IEEE-I394 R-t PC - rtpc12

Outputs available for connection:

- ieee-i394 7 IEEE-I394 R-t PC - rtpc02
- ieee-i394 7 IEEE-I394 R-t PC - rtpc03
- ieee-i394 7 IEEE-I394 R-t PC - rtpc04-mem issue
- ieee-i394 7 IEEE-I394 R-t PC - rtpc-roma
- ieee-i394 7 IEEE-I394 R-t PC - rtpc01
- ieee-i394 7 IEEE-I394 R-t PC - rtpc06
- ieee-i394 7 IEEE-I394 R-t PC - rtpc11
- ieee-i394 7 IEEE-I394 R-t PC - rtpc08

 Stop connecting

# Tools: Hardware Inventory


## Keeps track of part history

Contains also documentation (link to documentation system)

Data sheets, photos, measurement results, ...

### Worklog of a viewport
























Date	User	
16:24 24/09/08	maillet	Part attached to Wall-MC-W (97).
15:55 23/09/08	maillet	Part moved to: Wall-MC-W > Larson
11:59 17/09/08	maillet	On the polariscope, the viewport se
11:55 17/09/08	maillet	File  points (1).jpg (v001) attach
11:55 17/09/08	maillet	File  points.jpg (v001) attached f
11:55 17/09/08	maillet	File  Y01b.jpg (v001) attached to polariscope (45 degree rotation clo
11:54 17/09/08	maillet	File  Y01a.jpg (v001) attached to (engraved ID on the right, in the mi
11:54 17/09/08	maillet	File  Y01-vacuum-side.png (v001) vacuum side
11:54 17/09/08	maillet	File  Y01-air-side.png (v001) attached to this part. map of defects on air side
11:53 17/09/08	maillet	Dusty surfaces but no particular defect on air side. May have a bubble on vacuum side
11:52 17/09/08	maillet	Part added to database.



viewport characterization photo

[Code List](#)
[Add Code](#)
[View Series](#)
[Full Search](#)
[Help](#)
[Upgrades](#)
[Feedback](#)

Displaying Codes 1-20 of 9940 [1](#) [2](#) [3](#) [4](#) [5](#) [6](#) [7](#) [8](#) [9](#) [10](#) [End](#) [?](#)

Code <a href="#">?</a>	<a href="#">?</a>	Title <a href="#">?</a>	Date <a href="#">?</a>	Author(s) <a href="#">?</a>
VIR-0446A-15		Virgo Interferometer Channels DB (VIC) Update for Detchar	23/10/15	G. Hemming, L. Rolland, B. Swinkels, D. Verkindt
VIR-0445A-15		Commissioning planning for the STAC	23/10/15	B. Swinkels
VIR-0444A-15		Memorandum of Understanding between the Fermi GBM, the LSC, and VIRGO	22/10/15	Jordan Camp, Nelson Christensen, Peter Shawhan
VIR-0443A-15		TCS CO2 viewports investigation	22/10/15	TCS team
VIR-0442A-15	  	Planning for Central Interferometer commissioning preparation	21/10/15	Heitmann, F. Carbognani
VIR-0441A-15		CMake evaluation as CMT replacement at 03 Feb 2014 VDASC meeting	19/10/15	F. Carbognani
VIR-0440A-15	 	AdV weekly meeting minutes	17/10/15	H. Heitmann
VIR-0439A-15		VIRGO VSC meeting minutes, October 14th, 2015	19/10/15	Fulvio Ricci
VIR-0438A-15		Summary of Compensation Plate CP01 issue	19/10/15	L. Pinard
VIR-0437A-15		CWB Control Room Management System - Architectural Design Document	19/10/15	Lisa Zangrando
VIR-0436A-15		VDASC report to the STAC	19/10/15	Michele Punturo
VIR-0435A-15		Gabriela Gonzales, Albert Lazzarini, Dave Reitze, Fulvio Ricci	16/10/15	From Step 1 to STEP 2 of the DET. Proc.
VIR-0434A-15		PL report @CCB (Oct 7)	15/10/15	G Losurdo
VIR-0433A-15		Commissioning planning for the STAC	14/10/15	B. Swinkels
VIR-0432A-15		Commissioning planning for the VEB	14/10/15	Gianluca Gemme for the VEB
VIR-0431A-15		DA update	14/10/15	Chris Van Den Broeck
VIR-0430A-15		Communications to the VSC 14-10-2015	14/10/15	Fulvio Ricci
VIR-0429A-15		Draft Commissioning documents for the STAC	14/10/15	B. Swinkels
VIR-0428A-15		AdV report @VSC	14/10/15	G Losurdo
VIR-0427A-15		VDASC report to VSC	14/10/15	Michele Punturo

> 10.000 codes














Release control

Quick Search for a Code [?](#)

Title	<input type="text"/>
Author(s)	<input type="text"/>
Code	<input type="text"/>
Date from	<input type="text"/> (dd-mm-yyyy)
Date to	<input type="text"/> (dd-mm-yyyy)
<input type="button" value="CLEAR"/> <input type="button" value="SEARCH"/>	

Currently Highlighted Series [?](#)

User details [?](#)

Forename	heitmann
Surname	
Email	
<p><a href="#">?</a> You have access to files attached to Codes with the following Access Privileges:</p> <ul style="list-style-type: none"> <li> Public</li> <li> Virgo</li> <li> LSC</li> <li> STAC</li> <li> VSC</li> <li> Council</li> <li> AdV-MAN</li> <li> ELITES</li> <li> KAGRA</li> <li> PPPS</li> <li> ETRND</li> <li> GraWIToN</li> <li> VESF EB</li> </ul>	
<p><a href="#">?</a> You are a TDS Administrator</p>	
<p><a href="#">?</a> Your Default TDS Instance is: Virgo</p>	



Global AdV mpp planning was the reference for project data

- Global AdV WBS

- Cost
  - Cost distribution over labs, subsystems,...
  - Cost profile
  - Cost statistics during project evolution
- Manpower estimate
- Assignment of tasks to labs
- Budget structure

*Lessons learned: some of those tools have be less used than others. While introducing tools plan for long term sustainability*

- Heavy use of VBA scripting for automating work with planning

## SS WBS



SS.xls from  
SSM




Excel macros  
+ mpp



SS.mpp



Mpp  
macro




AdV.mpp

mpp  
macros for:  
plausibility  
checks,  
critical path,  
etc.

# Procurement Case: CB Scaffolding


- The Problem: a canonical (full permanent) scaffolding solution would have implied:
  - A complete rebuilt of the platform impacting the AdV planning
  - The creation of very strong infrastructural constraints for what concern foreseen or not yet foreseen CB equipment installation (Minitowers, Cryotrap, etc.) or others needs (towers displacement, etc.)



# Procurement Case: CB Scaffolding

## Draft executive design

- Integrated into overall CB 3D Design and early feedback provided to contractor



# Procurement Case: CB Scaffolding

- Good example of M-CAD Model based Engineering with very tight collaboration with contractor including several visit to contractor production plant.

- *Lessons learned: take your time to wisely select contractors even under tight planning constraints. The time you may waste with not appropriate choices will be much larger*

- *Lessons learned: the effort spent in building an integrated CAD design is well worth. Plan for the use of 3D laser scanners or photogrammetry for creating the models of your buildings/laboratories/plants in which the 3D CAD of the new components can be integrated.*
- *Making those models interactive with Virtual Reality (VR) headset technology would be best.*
- *We spent a non negligible time in correcting problems of mechanical incompatibilities that would have been immediately evident using VR walk troughs*


From late 2015 to late 2016 we experienced several monolithic suspension failures

Temporary solution: steel wires

After long investigations all the events were found correlated with vacuum operations: fast dust particles, produced during pumping/venting cycles, hit the fibers and produce the initial fracture


Several improvements to reduce high-speed dust effect will be implemented:

- Protection structures for the fibers
- Different paths for chamber venting
- New multistage root pumps substituting scroll pumps





# A Project "Crisis" Case: Monolithic Suspension Failure



- *Lessons learned: Problem investigation could greatly speed up once we had been able to reproduce the failure events on a separate test chamber which was late in its setup at the site. Never let your testing facilities lacking behind on the project schedule.*



# Conclusions

- The scientific community is eagerly awaiting AdV entering Science operations and join the international detectors network.
- Despite starting late and with less resources we have an operating detector and joining Ligo for the last part of the O2 Science Run is becoming a realistic goal
- We (The Virgo Collaboration and EGO) have been learning a lot during first and second generation detectors construction and we are ready for the third generation

# THANKS FOR YOUR ATTENTION!

For more information and for staying up to date on the VIRGO project:

<https://www.virgo-gw.eu/>